

# SP CONTRACTORS LLC

166 Walton Pl Lansdowne PA 19050 | Tel: 6102417493 Email:estimates@sp-contractors.com

[www.sp-contractors.com](http://www.sp-contractors.com)

| Category       | Code       | Description                 | Qty   | Unit |
|----------------|------------|-----------------------------|-------|------|
| Basement Walls | PNT-SPR    | Protect/mask contents (o    | 225.6 | SF   |
| Basement Walls | DPL        | Demo damaged plaster        | 225.6 | SF   |
| Basement Walls | PLS        | Plaster skim coat repair    | 225.6 | SF   |
| Basement Walls | PNT-PRM    | Prime walls                 | 225.6 | SF   |
| Basement Walls | PNT-WAL    | Paint walls (2 coats)       | 225.6 | SF   |
| Ceiling        | PNT-SPR    | Protect contents (occupie   | 90    | SF   |
| Ceiling        | DRY1/2D    | Remove plastered plywor     | 90    | SF   |
| Ceiling        | DRY1/2     | Install 1/2 drywall ceiling | 90    | SF   |
| Ceiling        | DRYF       | Finish drywall ceiling      | 90    | SF   |
| Ceiling        | PNT-PRM    | Prime ceiling               | 90    | SF   |
| Ceiling        | PNT-CLG    | Paint ceiling (2 coats)     | 90    | SF   |
| Exterior Step  | CONC-DEM   | Demo damaged step           | 1     | EA   |
| Exterior Step  | CONC-FRM   | Form step edges             | 1     | EA   |
| Exterior Step  | CONC-PATCH | Patch/rebuild step          | 1     | EA   |
| Exterior Step  | CONC-SEAL  | Seal concrete               | 1     | EA   |
| General        | CLN        | Final cleanup               | 1     | EA   |
| General        | MOB        | Mobilization                | 1     | EA   |
| General        | DUMP       | Debris disposal             | 1     | EA   |

| Summary               | Amount         | Trades Summary           | Amount      |
|-----------------------|----------------|--------------------------|-------------|
| Subtotal              | 6653           | Basement Walls Total     | 3011.76     |
| Overhead (10%)        | 665.3          | Ceiling Total            | 1071        |
| Profit (10%)          | 731.83         | Exterior Step Total      | 1595        |
| <b>Total Estimate</b> | <b>8050.13</b> | General Conditions Total | 975.24      |
|                       |                | <b>Sub Total</b>         | <b>6653</b> |

## Scope of Work

### **Basement Walls:**

Repair and plaster two basement wall sections measuring 16.6 x 8 and 11.6 x 8.

Total wall area 225.6 SF. Includes prep, plaster skim coat, priming, and painting.

### **Ceiling:**

Remove and replace existing plastered plywood ceiling (10 x 9 = 90 SF).

Install drywall ceiling, finish, prime, and paint.

### **Exterior Step:**

Repair one exterior concrete step including demo, forming, patching, and sealing.

### **General Conditions:**

Work performed in occupied space including protection, masking, daily cleanup, debris disposal, and final cleanup.

All work to match existing finishes as closely as possible.

| Unit Price | Total   |
|------------|---------|
| 0.85       | 191.76  |
| 3.1        | 699.36  |
| 6.1        | 1376.16 |
| 1.1        | 248.16  |
| 2.2        | 496.32  |
| 0.85       | 76.5    |
| 2.4        | 216     |
| 3.5        | 315     |
| 2.1        | 189     |
| 1.1        | 99      |
| 1.95       | 175.5   |
| 275        | 275     |
| 175        | 175     |
| 1050       | 1050    |
| 95         | 95      |
| 175        | 175     |
| 350        | 350     |
| 450.24     | 450.24  |

